

BUILDING REGULATIONS



KEY PLAN (FOR LOCATION ONLY)

P2	END OF RIVERSIDE RAMP AND STEPS UPDATED	YT	AR	27/04/25
P1	First preliminary issue. FORMAL ISSUE TO BUILDING CONTROL	YT	AR	05/01/24
Rev	Description	By	CB	Date



REVILL ARCHITECTS
AND
MASTER PLANNERS

T: 07436 393167
E: andrerevill@raamp.co.uk



Client MEDWAY DEVELOPMENT
COMPANY LTD

Project CHATHAM WATERFRONT
RIBA STAGE 4

Title	RAMP AND STEPS FROM RIVER WALK SIDE PLAN OVERLAY OF STRUCTURAL ENG'S PODIUM LAYOUT
-------	--

Status	Drawn By	PM/Checked by
PRELIMINARY	YT	AR

Job Ref	Scale @ A1	Date Created
18.037	1:50	23/12/24

RAAMP Drawing / Figure Number Rev
18.037-RAAMP-V1-00-DR-L-686-S3-P2

2

SLIP MEMBRANE 2m EITHER SIDE OF
MOVEMENT JOINT BETWEEN SLAB AND
CAPPING BEAM.
SEE SECTION 05 ON DRAWING 29004 FOR
INTENT

Ancon Shear Load Connector
To allow 60mm horizontal movement.
Characteristic Design Loads
Perm - 120kN/m
Var - 50kN/m

TPWCOL 2.16

Offset 0
on client ins.
23/02/2021

All gullies to be cast-in

All guided

02	RIVERSIDE WALK STEPS AND RAMP	
686	PLAN: PART 2 of 2	SCALE 1:50